The articles will be knocked down to the highest bidder, who should pay the amount immediately, failing which the articles will be put up for auction again at his risk.

1. One Oliver Typewriter (No. 11 55266).
2. One Underwood Typewriter No. 579273.
3. One Underwood Typewriter No. 447028.
4. One Remington Typewriter No. R. A. 85193.
5. One Camp Table.
6. One Table with double drawers.
7. One Revolving chair.
8. One Typist's chair.
9. One Bug proof chair.
10. One cushion chair.
11. One Bench.

M. S. MOHIYUDDIN,
Deputy Director.

OFFICE OF THE ASSISTANT ENGINEER, HEADQUARTER RANGE, MYSORE.

Notification dated 5th April 1937.

1. Sealed tenders will be received at the Office of the Assistant Engineer, Headquarter Range Mysore, up to 12 NOON on 20th April 1937, for converting the west end blocks of old Hutting Lines into Recruit Barracks at Mysore Horse, Mysore.

2. Tenders in the prescribed form obtainable from the Office of the Assistant Engineer, Headquarter Range, Mysore, on payment of Rupee one for each form, should be addressed to the Assistant Engineer, Headquarter Range, and should be superscribed as "Tender for converting the west end blocks of the Hutting Lines into Recruit Barracks at Mysore Horse, Mysore. The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender must be accompanied by a deposit of Rs. 160 (one hundred and sixty rupees only) in cash or Government Promissory Notes or Mysore Government Bonds at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract. (Cash amount will not carry any interest).

4. The tenders will be opened in the presence of such tenderers who wish to be present on 20th April 1937 at 3 P.M. The final acceptance of the tender will rest with the Assistant Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reasons whatever, for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Assistant Engineer's Office, in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the Agreement in the departmental schedule contract form for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. Copies of contract documents, estimates and drawings may be seen at any time at the Office of the Assistant Engineer, Headquarter Range, Mysore, on all working days between 11 A.M. and 5 P.M.

8. Specific rate should be given for each item in the schedule and the rates should be in rupees, annas and in multiples of three pies and expressed in words and figures. Tenderers offering a percentage increase or decrease on the estimate amount or estimated rates or the lowest tender will be rejected.

9. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates tendered should include all such lumpsum items.

10. No alterations which are made by the tenderers in the contract documents in the nomenclature of the sanctioned sub-heads will be recognised and if corrections are made, the tenders will be liable to rejection.

11. There should be no corrections or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

12. No reference should be made to the Public Works Department current schedule of rates.

13. On the event of the tender being submitted by a Firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power of attorney, authorising him to do so.

14. When once the rates tendered have been accepted they will not be revised under any circumstances. In regard to items of work not tendered, the rates to be proposed by the Assistant Engineer, Headquarter Range, Mysore, and approved by the Superintending Engineer, shall be final and legally binding on the tenderer.

15. The quantities given in the schedule are only approximate and are liable to alterations, omissions, deductions, or additions, at the discretion of the Assistant Engineer, or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

16. The work should be completed and handed over to the Public Works Department before the end of May 1937 failing which the Assistant Engineer may, at his discretion, levy a penalty of Rs. 30 per day, which will be recovered from the Contractor's outstandings for the period exceeded by him till the work is completed and handed over.

17. In all matters of dispute of any kind, not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer, shall be final and legally binding.

18. The earnest money of rejected tenders will be returned on submission of the receipts originally granted, along with an application, to the Assistant Engineer, Headquarter Range, Mysore.

19. No claims for damages, for delays caused by Officers of the Department in the execution of the work will be considered, whatever may be the reason for such delays. Contractors should bear this in mind when tendering for work. Extension of time due to delays caused by the departmental officers will however be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery, old doors, windows, etc., that will be supplied by the Assistant Engineer, in the interest of the work shall be accepted by the tenderer at the rates fixed by the Assistant Engineer, and the tenderers will pay the hire, etc., on machinery and tools and plant at the prescribed per cent per annum of the booked value of the tools and plant supplied from the date of taking over of tools and plant from the Stores to the date of return to the Stores. The dates considered being, the dates of acknowledgments of the vouchers in each transaction.

22. The contractors should arrange for the payment of Royalty and Tolls.

Note (*A*).—The Contractor should at his own cost—

(1) Provide rods, stakes, ropes and labours required in setting out the works.

(2) Provide all necessary scaffolding, centering labour and appliance for hoisting.

(3) Provide mortar mill and shed to keep materials under cover and also for workmen.

(4) Arrange for protecting work during inclement weather.

(5) Supply requisite temporary lights, water cisterns, water-shoots, coverings to masonry, tile pieces to steps, sieves, parahas, or measures storing and other requisite protection during the progress of the work.

(6) Supply all water required for work and workmen and shall provide latrines, drainages, etc.

(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.

(8) Provide arrangements for pumping and bailing from excavations and foundations, wherever and whenever necessary with his own pumping apparatus, including necessary leading drains, slump pits, etc.

(9) Wash floors at completion and leave the whole of the work and premises in a clean and orderly condition, etc.

(10) Afford facilities to any other parties employed upon the work so that their work may proceed during the progress of the contract and give such persons the use of ordinary scaffolding and ladders.

Note (*B*).—It is the business of the contractor to make his own arrangements for the quarries and supplies of materials.

23. The rates for wood work for all works quoted should be based on the rates of the departmental supply as noted below. Only Mysore Teak selected from the Mysore Depots must be used.

Prevailing Government rates at Mysore Forest Depot for—

	Rs.	a.	p.		
(1) Selected 1st class logs	2	8	0	per c.ft.	
(2) Cut scantling of sizes	3	4	0	„	for sizes 3″×4″.
(2) (*a*) Do	3	12	0	„	for sizes 3″×5″ to 4″×7″
(3) Planks 1″ to 1¼″ of required sizes	4	8	0	„	

Details of estimate for the work of constructing the West End Blocks of the Old Hutting Lines into Recruit Barracks at Mysore Horse, Mysore.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
	I.				
1	Dismantling brick masnory and carting debris including lead	C.ft.	..	11,362	
2	Burnt Brick in mud	„	..	849	
3	Chunam plastering ½″ thick smooth	Sqr.	..	44.20	
4	Teakwood work wrought and put up	C.ft.	..	169	
5	Providing and fixing new teakwood window frames size 3′×4′ with ½″ dia. iron bars, etc., complete, without shutters	S.ft.	..	144	
6	Removing burnt stone old slabs on doors and refixing on newly fixed doors	S.ft.	..	72	
7	Providing and fixing expanded metal with teak wood frames for windows of size 2½′×3′ and 3′×4′.	S.ft.	..	384	
8	Dismantling the existing paving in latrine and bath rooms	Sqr.	..	5.12	
9	Cement plastering the floor where portions of walls dismantled	Sqr.	L. S.	2.00	
10	Whitewashing two coats	„	L. S.	5.00	
11	Repairs to damaged floor with cement plastering ½″ to ¾″ thick	„	L. S.	5.00	
12	Painting with chocolate paint, two coats ..	„	L. S.	5.00	
13	Repairs to existing doors, windows, and Ventilators, etc., including iron fittings, etc., complete	No.	L. S.	6	
14	Carting the old doors to Stores and stacking them in the required place	No.	..	63	
15	Carting stone lintels to stores and stacking them in the required place	No.	..	51	
	II. Converting two houses of the Hutting lines into Dining rooms for Recruits.				
1	Dismantling brick work and carting debris including lead complete	C.ft.	..	1,240	
2	Burnt brick in mud with old bricks available ..	C.ft.	..	164	
3	Removing and refixing old door in altered positions including side brick work in chunam mortar and plastering and whitewashing, etc., complete	No.	..	3	
4	Providing new teakwood windows with ½″ dia. bars and iron fittings, etc., complete ..	S.ft.	..	12	
5	Chunam plastering smooth ½″ thick	Sqr.	..	2.62	
6	Fixing old burnt stone slabs for lintels over old door to be fixed on mortar bed	No.	..	3	
7	Removing the existing doors and carting to stores and stacking them in the required place including lead, etc.	No.	..	5	
8	Cement plastering ½″ thick	Sqr.	L. S.	5.00	
9	Removing old lintels and carting to Stores and stacking, including lead, etc., complete ..	No.	..	5	
10(*a*)	Whitewashings, two coats	Sqr.	L. S.	5.00	
(*b*)	Painting with chocolate paint, two coats ..	„	L. S.	5.00	
11	Removing the existing floor in bath room and latrine	Sqr.	..	0.32	
12	Providing teakwood bressummer including hoisting and fixing	C.ft.	..	22	

No.	Description of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
	III. Converting the existing Naick's Quarters into Kitchen.				
1	Dismantling brick masonry and carting debris including lead	C.ft.	..	851	
2	Brick in mud with old bricks available ..	„	..	406	
3	Chunam plastering ½" thick smooth	Sqr.	..	10.41	
4	Constructing oven with burnt brick in mortar for chimney arrangements, etc.	No.	..	1	
5	Removing and refixing teakwood doors old including side brick work and plastering, whitewashing, etc., complete	No.	..	4	
6	Removing and refixing burnt stone lintels on fresh mortar bed	„	..	4	
7	Providing and fixing teakwood bressummer, including hoisting, etc., complete	C.ft.	..	22	
8	Providing a sink of size 6'×4', etc., complete ..	No.	..	1	
9	Providing mortar and pestles of Chamundi Hill stone	„	..	2	
11	Painting with two coats of chocolate paint ..	Sqr.	L. S.	5.00	
12	Whitewashing, two coats	„	L.S.	5.00	

M. A. RAMANUJAM,
Assistant Engineer.

Printed by the Superintendent at the Government Press, Bangalore—1937